

Relax... You're in Safe Hands

Installations You Can Be Proud Of



www.greencirclewindows.com

Green Circle
Bespoke glazing

7 Reasons why you can trust us to carry out your installation...

Process	Green Circle Standard	Industry Norm	Consequence of Industry Norm
Installation of large span folding and sliding doors	1. High Quality Laser Level used to ensure a consistent level over large spans and across multiple door sets	6 foot spirit level used to level and line-up doors, (often much wider than 6 foot)	Doors much more likely to be out of level which could lead to operational and floor alignment issues
Delivery of large span folding or sliding door frames	2. We have a purpose built 5 metre trailer which we use to deliver fully fabricated outer frames directly to site	Outer frames are delivered to site in kit form for installers to assemble on site	Corner mitres can be uneven, sealing at corners can be patchy or easily missed altogether. Any missing or faulty components may only come to light at this stage
Attaching external cills to outer frame	3. External cills are sealed and fixed (without compromising drainage) to outer frames within clean, dry factory environment	External cills are attached to outer frames on site	More difficult to get cill level, sealing between frame and cill may be patchy or missing, cills likely to be attached by fixing down into sub-base increasing the chance of water ingress
Installation of oversize frames (7 Metres+)	4. Frames will be sent to site unmade, factory technicians will be on hand to ensure factory standards are maintained	Frames will be sent to site in kit form & Installers will be expected to assemble frames	Corner mitres can be uneven, sealing at corners can be patchy or easily missed altogether. Any missing or faulty components may only come to light at this stage
Method of contracting Installers	5. We use our own permanent PAYE installers to ensure they have a vested interest in the success of your project	Installers are sub-contracted	Installers may be more concerned with where their next job is coming from rather than the quality and longevity of your installation
Glazing	6. Transportation tape is removed from the edge of glazed sealed units to ensure the best possible seal between gasket and glass	Protective tape is not removed prior to glazing	Protective tape sits between gasket and glass and provides an opportunity for water to penetrate inner cavity of door or window frame, potentially causing premature failure of glazed units
Training and assessment	7. Our installers carry MTC cards proving they've passed an examination in surveying and installation overseen by the Glass and Glazing Federation (GGF)	Sub-contractors are relied upon to carry out their own training and on-site assessments	Unqualified or inexperienced installers may be sub-contracted to carry out the work of professionals

In Addition...

- We have been trading for over 40 years and have never failed to honour a guarantee!
- We stock 3, hard-wearing, scratch resistant profile finishes as standard!
- We manufacture your frames locally using advanced CNC machinery and stringent manufacturing processes.
- We have just completed the construction of a 2500 square foot storage and distribution centre to ensure your windows arrive in tip top condition
- We believe buying from us represents a long term Return on Investment.



Many thanks for the installation yesterday, which was completed to a high standard. We would also like to compliment the installation team on their polite and obliging manner.

Peter Wilkinson, Stoke Gabriel, Devon



Clearly Superior Installations

To book your own personal tour of our factory and showroom please contact us today:

01752 203203 | sales@greencirclewindows.com
www.greencirclewindows.com

Unit 5, Darklake Close, Estover Industrial Estate, Plymouth PL6 7TJ

